**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Fouth Dimension Group**
Lane No 8,Opp Axis Bank, Deccan Gymkhana
Pune, Maharashtra 411004

**Date :** 22.01.2021
**Quote NO :** SQT.20.21.2962
**Kind Attn :** Mr. Pankaj Kohale
**Email Id :** pankaj.kohale@fdgglobal.com
**Contact No:** 9371799815

**Subject : Quotation for High Speed Door-Fold up Doors**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Conditions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **High Speed Door-Fold up** | 10000 | 7000 | 1 | 650,000 | 650,000 | 25,000 | 25,000 |
| | | | | **Total** | | **650,000** | | **25,000** |
| 2 | P&F Charges | | | 3% | | 19,500 | | |
| | **Total Without Taxes** | | | | | 669,500 | | 25,000 |
| | GST Extra @ 18% | | | 18% | | 120,510 | | 4,500 |
| | **Total With Taxes** | | | | | **790,010** | | **29,500** |
| 3 | Transportation Charges | | | | | Extra at Actual | | |
| 4 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**HIGH SPEED FOLD UP DOOR**



| Sr. No. | Description | Specification |
|---|---|---|
| 1 | Product | High Speed Door-Fold up type ( All Imported Components ) |
| 2 | Opening Direction | Vertical |
| 3 | Mounting Location | Inside of the bay, inside the building |
| 4 | Opening/Closing Speed | 0.5m/Sec. -1.0m/Sec. |
| 5 | Wind Resistance | 90km/h – 110 km/h |
| 6 | Curtain Material | Curtain is in PVC made by anti-tear polyester fabric |
| 7 | Curtain Weight | 680 gr/sqm |
| 8 | Tensile Strength Warp/Weft (N/5Cm) | DIN 53354 - DIN EN ISO 1421/met. 1 – 2500/2500 N/50 mm |
| 9 | Stiffeners | Polycorbinate pipes |
| 10 | Tear Strength | Warp/Weft DIN 53363 – 250/250 N |
| 11 | Temperature range | -30°C +70°C |
| 12 | Flame Resistance | reaction in class 1 or 2 |
| 13 | Vision Panel | One row of transparent PVC windows, in rectangular size, assures a good visibility |
| 14 | Fabric Color | Standard Blue, Grey, Red, Optional with various colors |
| 15 | Fold Up Arrangement | Segmented PVC curtain is folded up through lifting belt & tube mechanism |
| 16 | Roller Shaft | Tubular pipes with lifting belts |
| 17 | Side Guide Rails | Self supporting Galvanized steel structure |
| 18 | Bottom Profile | PVC profile |
| 18 | Side Brackets | Galvanized steel brackets with bearings |
| 19 | Hood Cover (Optional) | Galvanized steel |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | |
| 4 | Any civil / masonry/structural work required | |
| 5 | All structure support required | |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | |
| 7 | Conduits, Cables required | |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

**With Best Regards**
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd