Sr. No.	Item	Specifications	Remarks
1.	Scissor Lift Type	**Hydraulic Scissor Lift with Power Pack**	
2.	Scissor Lift Tonnage Capacity and Size details	Up to 1500 Kgs. (maximum), Scissor Lift Size -1300 mm (L) X 630mm (W) X 705 (H) maximum	
3.	Scissor Lift Collapsed height from ground	250 mm	
4.	Scissor Lift maximum height from ground	700 mm	
5.	Scissor Lift Working Stroke	450 mm	
6.	Positional repeatability of Scissor Up/Down motion for component transfer	Within (+/- 0.1 mm)	
7.	Scissor Lift working stroke control & Overtravel protection	a. By pair of Limit Switches with stroke setting provision. b. Provision of mechanical hard stoppers during accidental overtravel.	
8.	Scissor Lift Up/Down speed	Maximum speed up to 1 meter/min adjustable with hydraulic flow control valve	
9.	Emergency Stoppage of Scissor Lift, Inching mode operation & Intermediate positions stoppage of Scissor Lift	a. Provision of power supply cut off during emergency stoppage. Inching mode b. Scissor lift operation with intermediate positions of ft to be achieved through hydraulic controls via operator Push Button control (Push Buttons & Electricals in client scope)	
10.	Hydraulic Scissor Lift safety requirements	a. Anti-trap bar provision during operator maintenance safety b. Third party Safe Working load certification is a mandatory requirement. c. Non-return Valve for fail safe overload protection d. Flexible bellows scissor lift skirt all around for protection against dust, chips and pinch joints.	
11.	Hydraulic Power Pack requirements	a. Power pack to be supplied using standard reputed elements Rexroth /Vickers/ Yuken. b. I. Hydraulic elements Makes, ii. Powerpack size, iii. Motor Specifications, iv. Valves Supply coil Voltages & v. Hydraulic Oil used to be specified in the drawing. c. Power pack to be compact in size as this has to be accommodated within a constrained available space of 600mm x 280 mm x 250mm (LX BXH)	
12.	Scissor Lift Top frame	Square tube structure 1300mm x 750mm x 705mm (LXBXH) with fabricated pads for mounting auxiliary's provision. Mounting details will be supplied during DAP	
13.	Scissor Lift Bottom frame	a. Square tube frame with grouting and levelling bolts provision of at least (+/- 10mm). b. Bottom frame shall have fabricated pad for mounting	

		Scanner camera bracket. Pad location & size details will be supplied during DAP.	
14.	Hydraulic Scissor Lift Preferred Makes (as per end user requirements)	a. Gear Pump- Rexroth/ Vickers/Yuken b. Hydraulic Cylinder – IPH c. Hydraulic Valves – Rexroth/Yuken/Vickers d. Power Pack Motor – Bharat Bijlee/ NGEF e. Pressure Switch (with visual indication & contact) - IFM f. Limit Switches - OMRON g. Proximity Sensors- P & F h. Pressure gauge Isolator – Hydax i. Hydraulic Filter- Yuken	Any deviations to be confirmed with prior approvals /agreements
15.	Hydraulic Scissor Lift Color Scheme requirements	a. Hydraulic Piping – Brown b. Scissor Lift Platform – Navy Blue c. Motor Electrical Cables – INPUT- Blue, OUTPUT- Red d. Motor Terminal Box – Safety Orange (RAL 2003 shade) e. Motor Fan guard – Red f. Pressure gauge – Green/Red Zone visual indication as per TPM Requirement g. All other areas of Scissor Lift- Grey White (RAL9002)	
16.	Equipment Documentation for approval & Handover	<u>Documentation required at the time of DAP approval</u>: a. Detailed GA Drawing with overall details covering all specified requirements in ACAD format b. Hydraulic Circuit with Detailed Bill of materials, makes & detailed specifications <u>Documentation required at the time of Handover (3 sets of hard copies and one set of soft copy):</u> a. Final GA Drawing after prove-out b. Hydraulic Circuit diagram c. Detailed BOM d. Spares parts list & Wear parts list e. Wear parts drawings f. Working Instruction manual	
17.	Hydraulic Scissor Lift Trials & Installation support	a. Functional proving of the scissor lift both during trials and at actual project site will be responsibility of supplier. b. All safety guidelines & Safe Process practices to be adhered to during proving of equipment. c. Equipment covers extended twelve months of warranty from date of dispatch of the delivered product with free replacement in case of field/installation site failures/malfunction.	