NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mobis India Limited
Plot No.E-1/1,MIDC,Additional Patlganga Industrial Area,
Village-Chavane,Taluka- Panvel,Raigad - 410207

Project, Location : Panvel

Date : 30.07.2021
Quote NO : SQT.20.21.3001R1
Kind Attn : Satyajit Bhoite
Email Id : satyajitbhoite@gmobis.com
Contact No: 8652831212

Subject : Revised Quotation for Dock Shelter - Inflatable

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY DS6070R inflatable dock shelter rollo**	2800	3000	2	569,000	1,138,000	Inclusive	
2	**ASSA ABLOY DS6070B inflatable dock shelter bags**	2800	3000	2	519,000	1,038,000	Inclusive	
3	**Uninstallation of Dock Shelter**			1	25,000	25,000		
4	**Dock Bumpers - D shaped**		Set	2	5,000	10,000		
	Total			**7**		**2,211,000**		
5	P&F Charges			3%		66,330		
	Total Without Taxes					2,277,330		-
	GST Extra @ 18%			18%		409,919.40		-
	Total With Taxes					**2,687,249**		**-**
6	Transportation Charges					Inclusive		
7	Unloading Charges @ Site					Inclusive		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY DS6070R inflatable dock shelter rollo

Sr .No.	Specification	ASSA ABLOY DS6070R inflatable dock shelter rollo (Imported - German Make)
1	Nominal Width	3200 mm
2	Nominal Height	4055 mm
3	Free Height	3600 mm
4	Nominal Depth	770 mm
5	Top bag extension	1000 mm
6	Side bag extension	650 mm
7	Walls insulated panel	42 mm
8	Fabric quality	PVC coated polyester
9	Top bag	500 g/m2, thickness 0,5 mm
10	Side bag rear	600 g/m2, thickness 0,5 mm
11	Side bag front	2500 g/m2, thickness 2 mm
12	Fan	230 V, 1-phase, 50 Hz, 250 Wnoise level: 65 dBA in workingposition
13	Operating	Switch control included
14	Temperature range	-30°C to +60°C

ASSA ABLOY DS6070B inflatable dock shelter bags

Sr .No.	Specification	ASSA ABLOY DS6070B inflatable dock shelter bags (Imported - German Make)
1	Nominal Width	3200 mm
2	Nominal Height	3755 mm
3	Free Height	3300 mm
4	Nominal Depth	770 mm
5	Top bag extension	1000 mm
6	Side bag extension	650 mm
7	Walls insulated panel	42 mm
8	Fabric quality	PVC coated polyester
9	Top bag	500 g/m2, thickness 0,5 mm
10	Side bag rear	600 g/m2, thickness 0,5 mm
11	Side bag front	2500 g/m2, thickness 2 mm
12	Fan	230 V, 1-phase, 50 Hz, 250 Wnoise level: 65 dBA in workingposition
13	Operating	Switch control included
14	Temperature range	-30°C to +60°C

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 13-14 weeks for Dock Shelter (ASSA ABLOY) from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd