NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

TCS
Sahyadri Park, Plot No. 2 & 3,
Rajiv Gandhi Infotech Park, Phase-III,
Hinjewadi, Pune

Date : 06.02.2021
Quote NO : **SQT.20-21.2448**
Kind Attn : Mr. Sitaram Naik
Email Id : sitaram.naik@tcs.com
Contact No: 9511212234

Project Name & Location: Battery Operated Mobile Crane, Pune

Subject : Quotation for Battery Operated Mobile Crane

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Testing & Commissioning Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Battery Operated Mobile Crane**	**1**	**17,50,000**	**17,50,000**	**10,000**	**10,000**
	Total			**17,50,000**		**10,000**
2	P&F Charges	3%		**52,500**		
	Total Without Taxes			**18,02,500**		**10,000**
	GST Extra @ 18%	18%		**3,24,450**		**1,800**
	Total Without Taxes			**21,26,950**		**11,800**
3	Transportation Charges					**Extra at Actual**
4	Unloading Charges @ Site					**Extra at Actual**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Battery Operated Mobile Crane

Parameters	Specification
Capacity	1 Ton
Overall Length	2495 mm
Overall Width	1150 mm
Overall Height	2160 mm
Boom Titing Up/Down	45°/ 10°
Boom Length (close)	2800 mm
Boom Extended	4000 mm
Drive Motor	2AC Kw
Lifting Motor	3Kw
Battery	24 / 480 V/Ah
Boom Operation	Hyadraulic
Parking Brake	EMB

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat 7410169333**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd