NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

NIHVA Sales Quotation

Conart Engineers Ltd.
Gujarat

Project, Location : Gujarat

Date : 26.12.2020
Quote NO : SQT.20.21.2899R2
Kind Attn : Daxa
Email Id : tenders@conartengineers.com
Contact No: 0265-2330946

Subject : Revised Quotation for Motorized Rolling Shutter and Insulated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**1.25mm MS Motorised Rolling Shutter - Direct Drive**	4000	4000	6	212,000	1,272,000	15,000	90,000
2	**1.25mm MS Motorised Rolling Shutter - Direct Drive**	3000	3000	2	168,000	336,000	15,000	30,000
3	**1.25mm MS Motorised Rolling Shutter - Direct Drive**	3000	2400	1	161,000	161,000	15,000	15,000
4	**1.25mm MS Motorised Rolling Shutter - Direct Drive**	3000	3600	1	176,000	176,000	15,000	15,000
5	**Double Wall MS Motorized Rolling Shutter with PUF Insulated - Direct Drive**	3000	2925	1	228,000	228,000	15,000	15,000
	Total			**11**		**2,173,000**		**165,000**
6	P&F Charges			3%		65,190		
	Total Without Taxes					2,238,190		165,000
	GST Extra @ 18%			18%		402,874.20		29,700
	Total With Taxes					**2,641,064**		**194,700**
7	Transportation Charges					Inclusive		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter - Direct Drive
1	**Description:**	Motorised Rolling Shutter with MS Slats with thickness of 1.25 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Control Panel**	Push button on both side
12	**Surface finish**	Synthetic Enamel Finish
13	**Drive Unit & Mounting Type**	Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection(European Make)

Double Wall Rolling Shutter (NIHVA Make)



Double Wall Rolling Shutter
• Thermal Insulation : Shutter infill of 20 mm PU rigid foam ensuring excellent thermal insulation
• Side guide Protection : Black plastic strips on the edge of the side guides protect against abrasion and ensure longevity of shutters
• Closing edge Safety device (only for Motorized) : Sensor controlled safety devices to monitor the bottom edge of the door. Instant stoppage and reversing on encountering any obstruction while closing .
• Sealing : Rubber seals are provided to reduce friction and sound, thereby ensuring a smooth door travel
• Accessories (Optional) : Vision panels for better visibility and light can be provided at extra cost
• Door Curtain : Aluminium curved slats
• Support Brackets : Galvanized steel
• Space Requirement (in mm) : Head room (S) = 675, minimum fitting depth for operator and support brackets (ET) = 450 (Space reqd for removal of cover is 2 times of cover) , Side space requirment (PS) = 210
• Minimum requirement for Building Structure : Concrete = 140 mm (Min strength M10) , Steel = 5 mm, Brick work = 240 mm (Min strength 100 kg/cm^2
• Side Guides : FS 160 A - moulded aluminium guide rails with guide channel, black plastic runner
• Bottom Profile : Extruded aluminium, Double skinned
• Seals : Lintel seal, Bottom seal made of EPDM profile
• Fixing Material : Tested and approved for steel, concrete, brickwork
• Operator : Shaft operator, Ready to fit shaft operator, Power Input - 1 phase current 0.25 kW, Protection category IP65 (jet water protected)
• Control : Integrated microprocessor control along with operator, Adjustable force limit and connection cable with CEE male plug in protection category IP 44, Push button on both side.
• Standard accessories : Chain Hoist and Shoot Bolt - for manual door
• Push Button : For Automatic Door

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune :

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd