NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/16-17/0504 **Date : 18-01-2017**

Bajaj Nagar, Waluj MIDC ,
Bil Road, Bil 391 410
Aurangabad
Maharashtra,India

Kind Attn : Mr. Ulhas Kukade
Email : unkukade@bajajauto.co.in
Contact No : 9822175908

Subject : Quotation for Bin Handling Trolley

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr	Description	Qty	Unit	Rate In INR	Net Amount INR
A	NIHVA Bin Handling Trolley with Stand On Platform Drawing as per attached	1	No.s	8,50,000.00	8,50,000.00
	Total				8,50,000.00

VAT TIN :	27545250455 V		**TOTAL BASIC AMOUNT**		**8,50,000.00**
CST TIN :	27545250455 C	**Amount in Words :**	**Rupees Eight Lacs Fifty Thousand Only**		
Service Tax No:	AAECN0437HSD001				

Technical Specifications			
Diamensions	Equipment Rated Capacity	:	150 Kgs
	Clamping Type	:	Manual
	Tilting Type	:	Hydraulic
	Tilting Direction	:	Forward
	Drum Type	:	BIN
	Tilting	:	130 Degree
	Overall Length	:	3000 mm
	Overall width	:	1600 mm
	Height (Including Mast)	:	1900 mm
	Ground Clearance	:	30 mm
	Drive Speed	:	4-5 kmph
Wheels	**PU Wheels :**		
	Load Wheel	:	Dia 83 x 70 mm
	Drive Wheel	:	Dia 230 x 70 mm
Drive	Lift Motor DC	:	2 KW
	Drive Motor AC	:	1.3 KW
	Battery	:	24/210 V/AH

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	8-9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply withing Maharshtra OR @2% CST against Form C (Outside Maharashtra)
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Mayur Derle** on **07709209333** For any further Clarification /Information in this Concern.

With Best Regards

Monika Kidgaonkar

8551091333

For Nihva Technologies Pvt Ltd