NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SEW BIZSOL
Pune

Date : 27.11.2021
Quote NO : **MHE_21.22.0046**
Kind Attn : Mr. Manoj Joshi
Email Id : marketing@sewbizsol.com
Contact No: 74994 50692

Project Name & Location: SEW BIZSOL, Pune

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation considering 03 people for 03 days per conveyor in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor** Total Length- 9.4 mtr Capacity- 20-30 boxes/min	**1**	**14,50,000**	**14,50,000**	**As per site we will discussed later**	
		Total		**14,50,000**		
	P&F Charges	3%		**43,500**		
	Total Without Taxes					**14,93,500**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	Transportation Charges					**Extra At Actual**
4	Insurance Charges					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Pharma Bags & Boxes
2	Product Size (L X B X H)	Box- 500 X 400 X 300 mm and Bags-900 X 500 X 200
3	Maximum Weight of Box/Bag	25 - 50 Kg
4	Capacity	20-30 boxes/min
5	Size of Belt	600 mm
6	Belt Type	PVC belt
7	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
8	Length Of Conveyor	Fixed Length : 4000 mm Telescopic (Expanded) : 5400 mm Total : 9400 mm
9	Main Body Of Conveyor	MS Powder coated
10	Lifting Mechanism	Hydraulic power packs
11	Highest feed height	1500 mm
12	Lowest feed height	600 mm
13	Drive Motor & Gear Box	SEW Make

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd