NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Address
Hyderabad

Date : 21.11.2020
Quote NO : SQT.19.20.2463
Kind Attn : Mr. P satyam Reddy
Email Id : psrprojects1234@gmail.com
Contact no.: 9618245700

Project Name & Location: Retractable Roof, Hyderabad

Subject : Quotation for Retractable Roof

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr no.	Description	Size	Qty	Supply and Installation Charges in INR	
			(Nos)	Unit Price	Total Amount
1	Retractable Roof	2200 mm (w) x 5300 mm (l) x 650 mm (h) - 3 segment	1	330,000	330,000
2	Retractable Roof	2000 mm (w) x 5400 mm (l) x 650 mm (h) - 3 segment	1	320,000	320,000
3	Retractable Roof	1200 mm (w) x 7000 mm (l) x 600 mm (h) - 3 segment	1	310,000	310,000
			Total		960,000
			P&F charges	**3%**	28,800
			Total Without Taxes		**988,800**
			GST Extra @ 18%	18%	177,984
			Total With Taxes		**1,166,784**
			Transportation Charges		**In Client Scope**
			Unloading Charges @ Site		**In Client Scope**

B) Technical Specification

1. Polycarbonate Israel Make compact clear, 4.0 mm Thick
2. Profile : Specially extruded Powder Coated AL Profile Frame (As per RAL colour)
3. Guide : Specially extruded Annodized AL Guide rails
4. Interlocking with Nylon Stopper
5. Dual Motors with Remote Control Movement **a) Single Phase Bi-directional Motor** **b) Speed- 09-12m/min** **c) Power- As per Roof Requirement** **d) Mechanical Limit Switch** **e) Rack and Pinion Arrangement -Z16/Molude4/Module6** **f) Italian Make BFT Brand**
6. Control Panel

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8-9 Weeks s from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply & 10 years warranty for polycarbonate sheets

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd